

15-097-00243-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1966
7-26-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Shell Oil Company
Complete Address: 1200 First National Bldg., Oklahoma City, Oklahoma
Lease Name Robbins Well No. # 1-21
Location C NW SE Sec. 21 Twp. 30 Rge. 16 (E) (W) W
County Kiowa Total Depth 4892'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: C. B. Smith Casing Pulling Company

Address: Box 1346, Cushing, Oklahoma License No. 205

Operation Completed: Hour 2:45PM Day 23rd Month July Year 1966

The Above well was plugged as follows:

531' of 8 5/8" surface pipe, cement circulated with 400 sacks. 4890' of 5 1/2" long string, cemented with 150 sacks. Plug back T.D. 4800'. Top perforation 4728'. Cast Iron bridge plug was set at 4500', and cemented with 3 sacks, through the dump bailer. 3720' of 5 1/2" long string was recovered from the hole. 15 sacks of Gel-Mud was pumped into the 5 1/2" at 720'. 30 Sacks of cement was pumped into the 5 1/2" at 510'. Hole was capped with 10 sacks of cement from 30' to the base of the cellar. Surface pipe was capped with a steel plate at the bottom of the cellar

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/26/66
INV. NO. 3633-U