

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-113-20450 ^{.00.00} (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR KC Development, done for Bryan Oil KCC LICENSE # 30111794
(owner/company name) (operator's)

ADDRESS RR1, Box 56 CITY Blount

STATE Kansas ZIP CODE 666851 CONTACT PHONE # (316) 382-3540

LEASE Bryan WELL# 1 SEC. 24 T. 19 R. 1 (East/west)

C-W2-NW4-SE4 SPOT LOCATION/QQQQ COUNTY McPherson

_____ FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

_____ FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 143 CEMENTED WITH 100 sacks SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 2982 CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2904-2956

ELEVATION _____ T.D. 2982 PBDT _____ ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING 100 sacks thru tubing
pipe + pull, Circulate from 250 to surface with
cement + 6% gel.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NONE IS ACCOMPANIED?

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Roy Savage or Theo Bond PHONE# 316 382-3540

ADDRESS RR1 Box 56 City/State Blount, KS

PLUGGING CONTRACTOR Company Pools KCC LICENSE # 30111
(company name) (contractor's)

ADDRESS _____ PHONE # () _____

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 8 AM -10-12-93 ?

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9-10-93 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 11 1993
CONSERVATION DIVISION
WICHITA, KS

2)

DECKER PETROLEUM CO.
BOX 352, CANTON, KS.

#1 BRYAN

24-19-1W
SW NW SE

CONTR TRIANGLE DRG. CO.

CTY MC PHERSON

GROL HARRY HOPKINS

FIELD BITIKOFFER NO.

1585 KA CM 7/22/77 CARD 1/12/78 IP F 275 MCFGPD + 17

BOPD + TR W
MISS 2904-31 OA

+	+	+
+	+	+
+	*	+

API 15-113-20,450

LOG	TOPS	DEPTH	DATUM
HEEB		2070	- 485
TOR		2086	- 501
DOUG		2097	- 512
IRELAND		2115	- 530
BR LM		2256	- 671
LANS		2317	- 732
BKC		2745	- 1160
PENN CONG		2878	- 1293
MISS		2904	- 1319
RTD		2984	- 1399

8-5/8" 143/100SX, 4 1/2" 2982
DST (1) 2916-40/30-30-30, GTS & FLO
52 MCFG (1ST OP) (2ND OP) FLO 7D
MCFG, 189' GCM, SIP 704-714#, FP
61-61#, 71-81#, BHT 106°
MCT - PF 2909-15, 2917-23, 2924-32,
AC 1000, SWB 3 BFPH, 15% OIL + 250
MCFGPD, POP, SQZ PFS W/115SX, RE-PF
2904-08, 2909-15, 2917-23, 2924-31,
AC 500, REC LD

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

October 13, 1993

KC Development Inc for Bryan Oil
RR 1 Box 56
Florence KS 66851

Bryan #1
API 15-113-20,450
C W/2 NW/4 SE/4
Sec. 24-19S-01W
McPherson

Dear Rex Savage or Theo Bond,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #2 202 W First Suite 304
Wichita KS 67202
(316) 263-8809

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238