15.009.00106.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

	X		



Locate well correctly on above Section Plat

Barton County. Sec. 29 Twp. 20 Rge. 12 (E) W (W)

Location as "NE/CNW¼SW¼" or footage from lines NE, NE, SW

Lease Owner Lafayette Oil Company

Lease Name Simpson Well No. 1

Office Address 125 West 3rd St Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-19 19 53

Application for plugging filed 6-19 19 53

Application for plugging approved 6-19 19 53

Plugging commenced 6-19 19 53

Plugging completed 6-20 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3586 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	232	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was filled with heavy mud to 230 feet and plug was set at 230 feet. 20 sacks of cement were then hand mixed and put through drill pipe on top of plug. Hole was then filled with heavy mud to 40 feet and plug was set, 10 sacks of cement were then hand mixed and put on top of the plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Schafer Drilling Company

Address Peoples Bank Building, Pratt, Kansas

STATE OF KANSAS, COUNTY OF PRATT, ss.

J. E. Selby (employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J E Selby

Pratt, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of June, 1953

Hilda Coulter
Notary Public.

My commission expires February 25, 1956

24-2675-S 2-52—20M

PLUGGING
FILE SEC. 29 T. 20 R. 12 W
BOOK PAGE 109 LINE 25

6-23-1953

15.009.00106.0000

Company: Lafayette Oil Co.
Contr: Schafer Drlg.
Sec 29-20-12W
NENESW

DRILLERS LOG
SAWYER #1

0-222	Sand & Gravel
222-654	Red Bed
654-665	Anhydrite
665-1010	Red Bed & Shale
1010-1475	Shale & Shells
1475-1625	Lime
1625-1750	Broken Lime
1750-1870	Shale & Lime
1870-1990	Lime
1990-2040	Shale
2040-2330	Shale & Lime
2330-2905	Shale
2905-2975	Shale & Lime
2975-3100	Lime
3100-3205	Shale & Lime
3205-3443	Lime
3443-3556	Conglomerate
3556-3586	Arbuckle
3586	TOTAL DEPTH

