


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Barton County, Sec. 31 Twp. 20 Rge. (E) 11 (W)  
Location as "NE/CNW%SW%" or footage from lines SE - SE - NE  
Lease Owner Meltzer Oil Company (M. and P. S.)  
Lease Name D. C. Johnson Well No. 1  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced \_\_\_\_\_ 5-14 19 59  
Plugging completed \_\_\_\_\_ 5-19 19 59  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3381 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	299	None
				4 1/2	3375	1605.94

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with sand from 3381' to 3360' - dumped 4 sks of cement - mudded hole to 300' - set 10' rock bridge - dumped 25 sks of cement - mudded hole to 40' - set 10' rock bridge - dumped 10 sks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 28 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R & D Casing Pulling Company License # 236  
Address Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. Nathan Meltzer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) \_\_\_\_\_  
Box 191, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of May, 19 59

My commission expires 3/30/61

Anne Meltzer  
Anne Meltzer Notary Public.

PLUGGING  
FILE SEC 31.20 R.11W  
BOOK PAGE 42  
41-1-30

15.009.14786.0000

Great Bend Pipe & Supply-D. C. Johnson #1  
SE SE NE Section 31-20S-11W  
Kowalsky Field  
Barton County, Kansas

Casing Record

8 5/8" cem 299 with 250 sax; cement settled  
50'; re-cemented around surface pipe with  
100 sax through 1" pipe; cement circulated.  
4 1/2" cem 3375 with 250 sax.

0 - 160 sand & shale  
300 sand, shale & red bed  
470 red bed & shells  
645 red bed, shale & shells  
1550 shale & shells  
1730 lime  
1925 lime & shale  
2085 shale & shells  
2383 lime & shale  
2390 shale  
2420 lime  
2460 shale  
2605 shale & lime  
2701 lime & shale  
2715 shale  
Top Topeka 2713  
2757 lime  
2838 lime & shale  
2960 lime  
3030 lime & shale  
3035 lime  
3125 shale & lime  
Top Lansing-Kansas City 3117  
3340 lime  
3368 lime & shale  
Top Simpson shale 3368  
3374 shale, green  
Top Arbuckle 3374  
3376 dolomite, with chert  
3381 dolomite T.D.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 19 1959  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 31 T 20 R 11W  
BOOK PAGE 38 LINE 42