

API NUMBER 15-009-24,529.0000

LEASE NAME Miller "B"

WELL NUMBER #1

4950 Ft. from (S) Section Line

840 Ft. from (E) Section Line

SEC. 35 TWP. 20 RGE. 11 (E) or (W)

COUNTY Barton

Date Well Completed 09-03-92

Plugging Commenced 09-03-92

Plugging Completed 09-03-92

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR L.D. Drilling, Inc.

ADDRESS RR 1 Box 183B Great Bend, KS 67530

PHONE#(316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 09-01-92 (date)

by Dave Wanda (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? \_\_\_\_\_

Producing Formation ----- Depth to Top ----- Bottom T.O. 3352'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To  | Size   | Put in | Pulled out |
|-----------|---------|------|-----|--------|--------|------------|
| surface   |         | 0.   | 479 | 8 5/8" | 479    | none       |
|           |         |      |     |        |        |            |
|           |         |      |     |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each section.

Bottom Plug: @ 3294' w/25 sacks cement thru drill pipe

Next Plug: @ 520' w/70 " " " " "

Top Plug: @ 40' w/10 " " " " "

15 sacks in rat hole

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc. RECEIVED

STATE OF KANSAS COUNTY OF BARTON STATE CORPORATION COMMISSION, SS.

L. D. Davis

~~(Employee or Operator)~~ (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well filed in the same are true and correct, so help me God.


(Signature) L. D. Davis

(Address) L. D. Davis

R.R. 1 Box 183 B

Great Bend, KS. 67530

Notary Public  
 Bessie M. DeWerff



SUBSCRIBED AND SWORN TO before me this 16th day of September, 1992

USE ONLY ONE SIDE OF EACH FORM

DRILLER'S WELL LOG

DATE COMMENCED: August 28, 1992  
DATE COMPLETED: September 3, 1992

L. D. Drilling, Inc.  
#1 MILLER 'B'  
150' E of NW NE NE  
Sec. 35, T20S, R11W  
Barton County, KS

ELEVATION: 1772 K.B.

- 0 - 471' Surface Soil, Clay, Sand
- 471 - 496' Anhydrite
- 496 - 1265' Shale
- 1265 - 1740' Shale w/lime streaks
- 1740 - 2533' Lime & Shale
- 2533 - 2906' Lime
- 2906 - 2936' Shale & Lime
- 2936 - 3030' Shale
- 3030 - 3053' Lime & Shale
- 3053 - 3288' Lime
- 3288 - 3304' Shale & Lime
- 3304 - 3352' Dolomite
- 3352' RTD


Surface Pipe: Set new  
8-5/8", 23# pipe @479'  
w/275 sacks 60/40 pozmix  
2% gel 3% cc.

**A F F I D A V I T**

STATE OF KANSAS  
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 10<sup>th</sup> day of September 1992.

  
RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public

SEP 21 1992

CONSERVATION DIVISION  
Wichita, Kansas