

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barton County, Sec. 35 Twp. 20S Rge. (E) 11 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. C N 1/2 S W NE

Lease Owner Lario Oil & Gas Company

Lease Name Otto Mueller Well No. A-2

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 28 19. 42

Application for plugging filed September 1 19. 42

Application for plugging approved September 2 19. 42

Plugging commenced September 2 19. 42

Plugging completed September 2 19. 42

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19. _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well C. F. Alexander

Producing formation none Depth to top _____ Bottom _____ Total Depth of Well 3360 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				<u>8 5/8</u>	<u>185'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was filled with mud from 3360' to 185', a permanent bridge was placed at 185'
and cement was used to 30', mud was used to 26' and cement to 6', mudded to top of
surface

35 20 11W
48 37

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lario Oil & Gas Company
Address 301 South Market Street
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Leo Ross

(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo Ross
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of September, 19. 42

My commission expires June 17, 1944
Margaret Brown
Notary Public.

9-28-1942

15.009.19478.0000

Commenced - 8-9-42
Completed - 8-28-42
T. Arwickle - 3319'
T.D. - 3360'
DVA

August 31, 1942

Log of Well - Otto Mueller "A" #2

C N 1/4 S W NE, 35-20-11W, Barton County, Kansas.

Surface	0 to 185'
Red Beds	185' to 460'
Sand	460' to 495'
Shale & shells	495' to 1455'
Lime	1455' to 1570'
Shale	1570' to 1632'
Lime	1632' to 1795'
Shale & shells	1795' to 1880'
Lime	1880' to 1845'
Shale & shells	1945' to 2254'
Sandy shale	2254' to 2380'
Shale & shells	2380' to 2490'
Sandy Shale	2490' to 2512'
Shale & shells	2512' to 2614'
Lime	2614' to 2652'
Shale	2652' to 2670'
Lime	2670' to 2818'
Sand	2818' to 2826'
Lime	2826' to 2923'
Shale & Shells	2923' to 3054'
Lime	3054' to 3302'
Shale	3302' to 3324'
Lime & Shale	3324' to 3360'

PLUGGING
FILE NO 35 20 R 11W
BOOK PAGE 48 NE 37

I, J. E. Trigg, Of Oklahoma City, Oklahoma do hereby certify that the above and foregoing is a true and correct copy of the well log of the Otto Mueller "A" #2 well as reflected by my records.

J. E. Trigg

Subscribed and sworn to before me this 1st day of September 1942.

Ruby Morrison

My commission expires

June 19, 1946

STATE REGISTRATION
COMMISSION
OCT 5 - 1942