

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-27316-00-00
Spot: N2S2N2NW Sec/Twnshp/Rge: 29-28S-17E
890 feet from N Section Line, 1320 feet from W Section Line
Lease Name: FAIL. W.O. Well #: 29-1
County: WILSON Total Vertical Depth: 1156 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1140		145 SX
SURF	8.625	20		5 SX
T1	2.375	1063		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 04/19/2018 10:30 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 04/19/2018 10:30 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to 1100 ft and the well was pumped full of cement from btm to top thru the cement string. The cement string was pulled to 200 ft and the well was again pumped full. The cement string was removed and the well topped off. According to operator, a total of 112 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
1021	1023		
977	979		
971	973		
835	837		
805	807		
736	739		
717	719		
649	653		
635	639		

RECEIVED
KCC DIST # 3
MAY 08 2018
CHANUTE, KS

AD

INVOICED

MAY 10 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning
(TECHNICIAN)