

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-26463-00-00
Spot: NWSESESE Sec/Twnshp/Rgc: 25-28S-17E
559 feet from S Section Line, 620 feet from E Section Line
Lease Name: CARTER, GREG A. Well #: 25-1
County: NEOSHO Total Vertical Depth: 1205 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1202		145 SX
SURF	8.625	23		5 SX
T1	2.375	1121		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 04/19/2018 2:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 205-8510

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 04/19/2018 2:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to 1100 ft and well pumped full of cement from btm to top. The cement string was pulled to 200 ft and the well pumped full again. The cement string was removed and the well topped off. The operator reported that 119 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
1051	1053		
1045	1047		
824	826		
784	787		
762	764		
695	699		
681	685		

RECEIVED
KCC DIST # 3
MAY 08 2018
CHANUTE, KS

AD

INVOICED

MAY 10 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning

(TECHNICIAN)