

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-133-26232-00-00  
Spot: SWNENENE Sec/Twnshp/Rge: 31-29S-19E  
657 feet from N Section Line, 648 feet from E Section Line  
Lease Name: KRAMER, JOHN A. Well #: 31-1  
County: NEOSHO Total Vertical Depth: 1029 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING, LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1024		120 SX
SURF	8.625	22		5 SX

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/12/2018 9:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 04/12/2018 9:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to 1000 ft and the well pumped full of cement from btm to top thru the cement string. The cement string was pulled to 200 ft and the well again pumped full. The cement string was removed and the well topped off. According to operator, 98 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
973	976		
920	922		
914	915		
546	550		
538	543		

RECEIVED  
KCC DIST # 3  
MAY 08 2018  
CHANUTE, KS

AD

INVOICED

MAY 10 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning  
(TECHNICIAN)