

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-20,927-0000  
SW<sup>1</sup>/<sub>4</sub>, Sec. 17, T 30 S, R 16 W<sup>1</sup>/<sub>2</sub>  
(NENE SW) feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

\_\_\_\_\_ feet from W/E section line

Operator License # 6313

Lease Name RICE Well # 1-17

Operator: CALVIN EXPLORATION, INC County KIOWA

Name & Address 1125 W 17TH, STE. 2000  
DENVER, CO 80202

Well Total Depth 4920 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 504

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor DAMAC DRILLING INC. License Number 6333

Address Box 1164, 625 WASHINGTON, GREAT BEND, KS 67530

Company to plug at: Hour: 4:00 AM Day: 17 Month: DEC Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO GALEN ROBERTS

(company name) DAMAC (phone) \_\_\_\_\_

were: use 50/50 Pozmix, 4% gel-3% CC and spot 1<sup>st</sup> Plug  
@ 960' w/10 sp. cmt.; 2<sup>nd</sup> plug @ 630' w/40 sp  
cmt.; 3<sup>rd</sup> plug @ 40' w/solid bridge of hulls and  
8 5/8 plug; 4<sup>th</sup> from 40'-0' w/10 sp. cmt.; 5<sup>th</sup> in  
rathole and mousehole w/10 sp. each circ.

Signed R. Barbutan  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:15 AM Day: 17 Month: DEC Year: 1982

ACTUAL PLUGGING REPORT Plugged as ordered.

Cementing by Halliburton.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 29 1982

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Anhydrite top @ 800'

12-29-1982

I hereby certify that the above plugging instructions were given as herein stated  
and that I (~~did~~ / did not) observe this plugging.

INVOICE Signed R. Barbutan  
(TECHNICIAN)

DATE 1-13-83  
INV. NO. 2138-W

FORM CP-2/3  
Rev. 9-82

\$159.90