

3-5

62-040590

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-113-20,155.00.00

NW SE SW, SECTION 3 TOWNSHIP 19 RANGE 2W

OPERATOR LICENSE # 5663 990 FEET FROM S SECTION LINE
3630 FEET FROM E SECTION LINE

OPERATOR Hess Oil Company
NAME & P. O. Box 1009
ADDRESS Mcpherson, KS 67460

LEASE NAME: Nelson #8
COUNTY: McPherson

WELL TOTAL DEPTH: 2962' 96.20

CONDUCTOR PIPE: " @ '
SURFACE CASING: 8-5/8" @ 150'

ABANDONED OIL WELL GAS WELL INPUT WELL SLD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Hess Oil Company
ADDRESS: _____ LICENSE: _____

COMPANY TO PLUG AT: HOUR: 3:30 DAY: 5 MONTH: 3 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Brian Hess
COMPANY NAME: Hess Oil Company PHONE: _____

WERE: Sand bottom - try to recover 5-1/2" & go from there.

PLUGGING PROPOSAL RECEIVED BY: Ralph Tittel

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 4:00p DAY: 5 MONTH: 3 YEAR: 1991

ACTUAL PLUGGING REPORT:

Had trouble w/well - ran tubing & packer to clean out & swab - bottom plugged off - tried to acidize - ate tubing off 3 jts above packer @ 2900' - sanded to 2800' c/w/5 sx cmt - recovered 1200' of 5-1/2" - bailed dry to 300' - built solid bridge & filled to surf w/redimix slurry, 5 yds - checked top plug on 3/6/91 - O.K. 3-12-1991

REMARKS: _____

I DID OBSERVE THIS PLUGGING.

INVOICED

Ralph Tittel
Ralph Tittel (AGENT)

MAR 12 1991
CONSERVATION DIVISION
Wichita, Kansas

DATE 3-15-91
INV. NO. 31175

FORM CP-2/3
REV. 3/90

ow 3-5



Kansas Corporation Commission

Joan Finney
Governor

Jim Robinson
Chairman

Keith R. Henley
Commissioner

Rich Kowalewski
Commissioner

Judith McConnell
Executive Director

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

March 6, 1991

Hess Oil Company
P.O. Box 1009
McPherson, KS 67460

Nelson #8
NW SE SW 03-19-02W
McPherson County, KS
API No. 15-113-20,155.00.00

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #2, 202 W. First, #304
Wichita, KS 67202
(316) 263 - 8809

Conservation Division
Shari Feist Albrecht
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238