

1 120798

6-11

15. 145. 00318.00.01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 1981

SW SW SW , SEC. 35 , T 23 S, R 18 W/E
330 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5290

Lease Name Bender Well # 1

Operator: Hinkle Oil Company

County Pawnee

Name & Address 1016 Union Center Bldg.

Well Total Depth 4555 148.03 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 11 a.m. Day: 11 Month: 6 Year: 19 93

Plugging proposal received from Kenny Gates

(company name) Pratt Well Service (phone) 316-672-2531

logs: 4 1/2" at 4547' w/200 sx cement, PBTD 4526', Perfs at 4416-22', Squeezed perfs at 4079-83'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p.m. Day: 11 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 700 psi and shut in 150 psi.

RECEIVED STATE CORPORATION COMMISSION

JUN 16 1993 6-16-1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2610' of 4 1/2" casing.

INVOICED

Additional description is necessary, use BACK of this form

I (did / observe) this plugging.

DATE: 6-22-93

Signed Duane Rankin (TECHNICIAN)

INV. NO. 37970