

To: 1 120981 10-21  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-21,274 . 00.00  
SW NE NE, SEC. 17, T 23 S, R 18 W/E  
4290 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4067  
Operator: TKO Investment Co., Inc.  
Name & Address Rt. 1, Box 394  
Dodge City, KS 67801

Lease Name Nuss Well # 1  
County Pawnee 146.25  
Well Total Depth 4500 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Peters Drilling Co., Inc. License Number 3400  
Address P.O. Box 742, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 21 Month: 10 Year: 19 94

Plugging proposal received from Mike Peters  
(company name) Peters Drilling Co., Inc. (phone) 316-793-6721

Work: 5 1/2" at 4495' w/155 sx cement, PBD 4428', Perfs at 4406-10'  
1st plug sand 5 1/2" casing back to 4350' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 21 Month: 10 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4350' and dumped 5 sx cement  
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Pumping pressure 0-800 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2230' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (and ~~XXXXXX~~) observe this plugging.

Signed Glenn Barlow  
(TECHNICIAN)

INVOICED  
DATE 11-7-94  
INV. NO. 41599  
10-21

STATE CORPORATION COMMISSION  
OCT 26 1994  
10-26-1994  
WICHITA, KANSAS