

1090366

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 187-20,393 .00.00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363 5364

Operator: Berexco-Beren
Name & Address: 970 Fourth Financial Center
Wichita, KS 67202

apprx. S/2 NE NW SEC. 15 T 30 S, R 41 W/X

4380 feet from S section line

3280 feet from E section line

Lease Name Elizabeth Well # 2

County Stanton 181.03

Well Total Depth (Mississippi) 5570 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1565

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 12:00 pm Day: 1 Month: July Year: 19 85

Plugging proposal received from Stan Wycoff

(company name) Beredco (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1540
Elevation 3355

1st plug at 1620' with 60 sx cement

2nd plug at 700' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:00 pm Day: 1 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1620' with 60 sx cement, 2nd plug at 700' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
7-9-85

Remarks: Used 60/40 Pozmix 6% gel by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

(if not observed) observe this plugging.

DATE 7-17-85

Signed Robert B. Tarbutton
(TECHNICIAN)

INV. NO. 8990