

1 050444

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 187-20,831 . 00.00
50' E & 20' N
E/2 NW SE, SEC. 19, T 30 S, R 41 W/EX
2000 feet from S section line
1370 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363 & 5364
Operator: Berexco/Beren Corporation
Name & Address 970 Fourth Financial Building
Wichita, KS 67202

Lease Name Bramlett Well # 1-19
County Stanton 182.00
Well Total Depth 5600 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1516 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Beredco, Inc. License Number 5147
Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 1:00 pm Day: 3 Month: February Year: 19 85

Plugging proposal received from Jim Maloney
(company name) Beredco, Inc. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 1550' with 40 sx cement
2nd plug at 780' with 40 sx cement
solid bridge
3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement
5th plug to circulate rat hole with 10 sx cement
6th plug to circulate mouse hole with 10 sx cement.
Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 2:00 pm Day: 3 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1550' with 40 sx cement, 2nd plug at 780' with 40
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to
circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
2-7-1985
FEB 07 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Dowell
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-13-85
INV. NO. 6950
2-3

Signed Richard W. Lacey RD
(TECHNICIAN)