

1 110158

10-12

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 187-20,462 . 00.00
C NE SE, SEC. 5, T 30 S, R 42 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4782

1980 feet from S section line
660 feet from E section line

Operator: Ensign Operating Company
Name & Address 621 17th Street, Suite 1800
Denver, CO 80293

Lease Name Hoopingarner Well # 1-5
County Stanton 185.25

Well Total Depth 5700 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1537

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 7 a.m. Day: 12 Month: 10 Year: 19 89

Plugging proposal received from Reed Wacker

(company name) Ensign Operating Company (phone) 316-276-3267
Elevation 3526'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1500-36'

1st plug at 2860' with 100 sx cement, 2nd plug at 1560' with 50 sx cement,

3rd plug at 780' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Mike Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 1 p.m. Day: 12 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2850' with 100 sx cement,

2nd plug at 1580' with 50 sx cement,

3rd plug at 780' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1989 11-17-1989

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

RAW

DATE 11-20-89

Signed James R. Kray
(TECHNICIAN)

INV. NO. 26535

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 9 15 89
month day year

c NE SE Sec 5 30S 42 East
S, Rg X West

OPERATOR: License # 04782
Name: Ensign Operating Co.
Address: 621 17th Street, Suite 1800
City/State/Zip: Denver, Colorado 80293
Contact Person: L. T. Hartnett
Phone: (303) 293-9999

1980' feet from South line of Section
660' feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5107
Name: H-30 Drilling Inc.

County: Stanton
Lease Name: Hoopinger Well #: 1-5
Field Name: D.V. W. N.

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
X Gas ... Storage ... Pool Ext. ... Air Rotary
... O.W.O ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes X no
Target Formation(s): St. Louis
Nearest lease or unit boundary: 660'
Ground Surface Elevation: 3526' feet MSL
Domestic well within 330 feet: ... yes X no
Municipal well within one mile: ... yes X no
Depth to bottom of fresh water: 480'
Depth to bottom of usable water: 580'
Surface Pipe by Alternate: X 1 ... 2
Length of Surface Pipe Planned to be set: 1600'
Length of Conductor pipe required: 5700'
Projected Total Depth: 5700'
Formation at Total Depth: St. Louis
Water Source for Drilling Operations:
X well ... farm pond ... other

If O.W.O: old well information as follows:
Operator: ...
Well Name: ...
Comp. Date: ... Old Total Depth ...

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, total depth location: ...

DWR Permit #: ...
Will Cores Be Taken?: ... yes X no
If yes, proposed zone: ...


Spud 10-2-89 Surf 1600
600' Alt. I Req.

AFFIDAVIT

PUSHER Reed W
TD 5700 FORMATION St. Louis
SURFACE PIPE 8 3/8 @ 1536
ANHYDRITE 1536 ELEVATION 3526
Hwy 200 & 400 - 2600 to 2880
STARTING TIME & DATE 10/12/89 7 AM

COMPLETION TIME & DATE 1 PM
1st PLUG @ 2860 FT. W/ 100 SX
2nd PLUG @ 1560 FT. W/ 50 SX
3rd PLUG @ 780 FT. W/ 50 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ Cement
CEMENT COMPANY Halliburton
TECHNICIAN M.W
TYPE OF CEMENT 60/40 w/60/90

276-3267



RECEIVED
NOTE: Complete this form within 5 days of effective date.
Spud date: _____ Agent: _____

NOV 17 1989

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - CONSERVATION DIVISION Form ACO-1 within 120 days of spud date;
 - Obtain lease/acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.

42w