

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAR 31 1964

3-31-64

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Cory of Superior Oil Company has this

date requested permission to plug the following described well:

Mr. Cory guarantees payment of the plugging fee.

Operator's full Name: Superior Oil Company

Complete Address: Box 200 Casper, Wyoming

Lease Name: Weaver Unit Well No. # 2

Location: C SW/4 Sec. 35 Twp. 30S Rge. (E) (W) 42

County Stanton Total Depth 5258' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Cory was instructed to plug the well as follows:

8 5/8"-1518' Circulated w/cement. 4 1/2"-5258' Cemented w/200 Sax.cement.

Perforations 5216' to 5230' Plug back to 5234'

Plug bottom w/sand 5234' to 5200' 5 Sax.cement 5200' to 5140'

Mud 5140' to 1530' 50 Sax.cement 1530' to 1380'

Pulled 2460' 4 1/2" pipe. Well to be used as a disposal.

Very truly yours,

Hugh Scott
 Conservation Division Agent