

State of Kansas



15.187.10032.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of The Superior Oil Co. has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: The Superior Oil Company

Complete Address: Box 200, Casper, Wyoming

Lease Name: Weaver Unit Well No. 1

Location: C NW/4 Sec. 35 Twp. 30 Rge. 42 ~~W~~ (W)

County Stanton Total Depth 5335' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

10 3/4" to 1518' circulated w/ cement. 7" casing to 5335' cemented.


Top perforations 5203' Plug bottom w/ 25 sacks cement,

Top of cement 4762' Mud 4762' to 800'

Spotted 50 sacks cement 800' to 700' Mud 700' to 35'

Plug, Hulls & 15 sacks cement 35' to 0'

Very truly yours,


Conservation Division Agent