

State of Kansas



15.187.10002.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1969
CONSERVATION DIVISION
Wichita, Kansas

5-26-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Grubbs of Colo. Oil Co. has this

date requested permission to plug the following described well:

Mr. Grubbs guarantees payment of the plugging fee.

Operator's full Name: Colorado Oil Company

Complete Address: 915 Union National Bldg., Wichita, Kansas,

Lease Name: Santa Fe Well No. 1-35

Location: G-SE Sec. 35 Twp. 30 Rge. 42 (E) (W)

County Stanton Total Depth 5300' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Grubbs was instructed to plug the well as follows:

8 5/8" to 1511' circulated w/ cement. 5 1/2" to 5284' cemented.

Top perforations 5226' Plug bottom w/ 25 sacks cement/

Top of cement 5100' Mud 5100' to 900'

Spot 40sacks cement 900' to 780' Mud 780' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent