



15-187-00025-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1968
CONSERVATION DIVISION
Wichita, Kansas

8-15-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dungan of Superior Oil Company has this
date requested permission to plug the following described well:

Mr. Dungan guarantees payment of the plugging fee.

Operator's full Name: Superior Oil Company

Complete Address: Box 200, Casper, Wyoming

Lease Name: R.H.C. Unit Well No. 1

Location: C NE Sec. 33 Twp. 30 Rge. 42 (W)

County Stanton Total Depth 5356' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Dungan was instructed to plug the well as follows:

10 3/4" to 1527' circulated w/ cement. 7" to 5352' cemented.

Top perforations 5252' Plug bottom w/ 25 sacks cement

Top of cement 5000' Mud 5000' to 900'

Spotted 50 sacks cement 900' to 750' Mud 750' to 35'

Plug, Halls & 15 sacks cement 35' to 0'.

Very truly yours,

Conservation Division Agent