



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1973
CONSERVATION DIVISION
Wichita, Kansas
2-28-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Ashland has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Ashland ~~Oil~~ Exploration Company

Complete Address: Box 18695, Oklahoma City, Oklahoma

Lease Name: C.D. Weaver Well No. 1

Location: C NW Sec. 28 Twp. 30 Rge. 42 ^{XX} (E) (W)

County: Stanton Total Depth 5373' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1520' circulated w/ cement. 5 1/2" to 5372' cemented.

Top Perforations 3140' Plug bottom w/ 25 sacks cement.

Top of cement. 3030' Mud 3030' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent