

State of Kansas



WM. H. AVERY Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 20 1967

3-20-67

CONSERVATION DIVISION  
 WICHITA, KANSAS

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

Dear Sir:

Mr. Clarence Courange of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Courange guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas

Lease Name: Kane Unit Well No. # 1

Location: App. C SW Sec. 8 Twp. 30 Rge. 17 (E)(W) W

County Kiowa Total Depth 4845' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Courange was instructed to plug the well as follows:

506' of 8 5/8" surface pipe, cement circulated with 400 sacks. Fill hole with drilling mud to 400', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat & mouse hole with 4 sacks

Very truly yours,

Archie Elving  
 Conservation Division Agent