

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

7-3-82

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Elmo Morganstern of Clark Corporation has this date requested permission to plug the following described well:

Operator's Full Name: Petroleum Inc.

Complete Address: Suite 800 R.H. Jarney Bldg. 300 West Douglas Wichita, Kansas 67202

Lease Name: Banton Well No. C-2

Location: 125° S NL - 16 20' W EL NE Sec. 20 Twp. 30 Rge. 17 (E) (M)

County: Keowa Total Depth: 5015'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Morganstern was instructed to plug the well as follows:

They cement circulated 518' of 8 1/2" surface casing. They ran 5013' of 5 1/2" production pipe plugged back to 4937'. Then perforated it from 4808' to 19'. 1st plug sand off bottom back to 4780' + put 5 sby of cement on top of it with salou. 2nd plug 5 sby bulls 25 sby of gell & released rubber plug and pumped 150 sby of cement. This cement used way ^{common} ~~over~~ _(over)

Very truly yours,

Paul A. Luther
Conservation Division Agent

with 2% gel & 3% C.C. They recovered 3400' of $\frac{5}{8}$ "
production pipe. The plugging was accomplished
by Sun Cementing. Shut in pressure was 500 lb.

Paul A. Luthi