



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

RECEIVED
STATE CORPORATION COMMISSION

JUL 30 1962

CONSERVATION DIVISION
Wichita, Kansas

7-30-62

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date July 26, 1962, 1962, authorized the following plugging operation:

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 Fourth National Bk. Bldg.

Lease Name: Rice #1 Well No. 1

Location: 150' South of Cen. Sec. 1 Twp. 30 S Rge. 17 (E) (W) x

County: Kiowa SE SE Total Depth: 4975'

Oil Well Gas Well Input Well SWD Well

D & A Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

322' of 8 5/8" surface pipe circulated with 200 sacks cement
Hole filled with heavy drilling mud to 240', 1/2 sack hulls and
1st cementing plug, 25 sacks cement through drill pipe. Hole
filled to 40' with heavy drilling mud, 1/2 sack hulls & 2nd
cementing plug, 10 sacks cement to bottom of cellar, rathole
bridged and 2 sacks cement.

Very truly yours,

Herman Justus

