

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-187-20,299.00.00

LEASE NAME Hudgens

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1320 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 32 TWP. 30 RGE. 42 XXXXX (W)

LEASE OPERATOR Kansas Petroleum, Inc.

ADDRESS 225 N. Market, #310; Wichita, KS 67202

COUNTY Stanton

PHONE#(316) 267-2266 OPERATORS LICENSE NO. 5023

Date Well Completed 12/18/78

Character of Well Gas

Plugging Commenced 2/4/87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/4/87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City (Glen Barlow)

Is ACO-1 filed? Yes If not, is well log attached? Previously submitted

Producing Formation Krider Depth to Top 2160' Bottom --- T.D. 2240'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Krider	gas-water	2160'	2190'	8 5/8"	646'	0-cement circ
				5 1/2"	2235'	0 (cement from TD to
						surface behind 5 1/2" casing

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Halliburton pumped down 5 1/2" casing with 2 sx hulls mixed with 20 sx HLC cement w/ 6% gel - followed by 115 sx HLC cement w/ 6% gel - pressured to 1200#. 5 1/2" casing is full of cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. ---

Address Lamar, Colorado

STATE OF Kansas COUNTY OF Seward, ss.

Terry W. Maxwell (Employee of Operator) XXXXXXXXXX of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W Maxwell


(Address) P. O. Box 6; Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 19 87

Edna M. Parish
Notary Public 2-24-1987

My Commission Expires: 2-19-89

FEB 24 1987



CONSERVATION DIVISION Form CP-
Wichita, Kans. Revised 08-8.