

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-187-20,385-00

LEASE NAME Rorick

WELL NUMBER 1

SPOT LOCATION approx C NW

SEC. 18 TWP. 30S RGE. 42W (~~E18W~~)

COUNTY Stanton

Date Well Completed 2-8-85

Plugging Commenced 2-8-85

Plugging Completed 2-8-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Midco Exploration, Inc.

ADDRESS 200 E. First, Suite 411, Wichita, KS 67202

PHONE # (316) 267-3613 OPERATORS LICENSE NO. 5254

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 5500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

Formation	Content	From	To	Size	Put in	Pulled out
				8.5/8"	1475'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st plug @ 1530' w/ 50 sx, 2nd plug @ 810' w/ 40 sx, top plug @ 40' w/ 10 sx, rathole 15 sx; 115 sx 60/40 poz, 3%cc, 2%gel, plug down @ 4:30 p.m. 2-8-85

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mustang Drilling & Exploration, Inc. License No. 5652


Address P.O. Box 1609, Great Bend, Kansas 67530 3-6-1985

STATE OF Kansas COUNTY OF Barton, ss.

Bill Nelson (employee of operator) or MAR 06 1985
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bill Nelson

(Address) P.O. Box 1609, Great Bend, KS



SUBSCRIBED AND SWORN TO before me this 1st day of March, 1985

Pamela K. Walters
Notary Public
Pamela K. Walters

My Commission expires: August 25, 1987

15,187.20385.00.00

Midco Exploration, Inc.
Rorick #1
Stanton, County, Kansas

DRILLERS LOG

Sand, Clay	0	648
Sand, Shale	648	1045
Shale	1045	1108
Anhydrite	1108	1123
Shale, Sand	1123	1474
Shale	1474	1483
Shale, Clay	1483	1758
Lime, Shale	1758	2116
Shale, Lime	2116	2672
Lime, Shale	2672	5500
RTD		5500

RECEIVED
STATE CORPORATION COMMISSION

MAR 06 1985

CONSERVATION DIVISION
Topeka, Kansas