

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-187-20,374.00.0

LEASE NAME Johns

WELL NUMBER 1-26

SPOT LOCATION C SW SW

SEC. 26 TWP. 30S RGE. 41W (~~EXX~~W)

COUNTY Stanton

Date Well Completed 9-30-84

Plugging Commenced 9-30-84

Plugging Completed 9-30-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mustang Drilling & Exploration, Inc.

ADDRESS P.O. Box 1609, Great Bend, KS 67530

PHONE # (316) 792-7323 OPERATORS LICENSE NO. 5652

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation --- Depth to top _____ bottom T.D. 5608'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	1567'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st plug @ 1570' w/ 50 sx, 2nd plug @ 800' w/ 50 sx, top plug @ 40' w/ 10 sx, rathole 15 sx; 125 sx 60/40 poz, 2% gel, 3%cc Dowell plug down @ 12:15 p.m. 9-30-84.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mustang Drilling & Exploration, Inc. License No. 5652
Address P.O. Box 1609, Great Bend, KS 67530

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.


Bill Nelson (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That

I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bill Nelson

(Address) Bill Nelson
P.O. Box 1609, Great Bend, KS

OCT 24 1984
10-24-1984
CONSERVATION DIVISION
Wichita, Kansas



SUBSCRIBED AND SWORN TO before me this 20th day of October, 19 84

Pamela K. Walters
Notary Public
Pamela K. Walters

My Commission expires: August 25, 1987

15.187.20374.00.00

SIDE TWO

Operator Name Mustang Drilling & Exploration, Inc Lease Name Johns Well # 1-26

Sec..... 26 Twp..... 30S Rge..... 41W East West County..... Stanton

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken Yes No
Samples Sent to Geological Survey Yes No
Cores Taken Yes No

Formation Description
 Log Sample

Drill stem tests attached.

Heebner - Sh. black, carbonaceous.
Lansing -Ls. white, gray, gray/brown, very fine crystalline, fossiliferous, oolitic in sections w/ some oocastic porosity, no shows, no stain.
Morrow -Sh. black, gray, carbonaceous.
Morrow -Sd. white, gray, glauconitic, very fine grained, hard, shaley, no shows, no stain.
Keys - Sd. white, gray, glauconitic, predominately fine grained clusters, sub-angular, fair sorting, intergranular porosity, show of gas and oil, no odor, no stain, trace of fluorescence.
Mississippian -Ls. white, gray/brown, sand, oolitic, no shows, no stain.

Name	Top	Bottom
Heebner	3668	- 272
Lansing	3789	- 393
B/Kansas City	4230	- 834
Morrow Shale	5011	-1615
Upper Sand	5165	-1769
Middle Sand	5376	-1980
Keys Sand	5470	-2074
Mississippi	5522	-2126

RECEIVED
STATE CORPORATION COMMISSION

OCT 24 1984

CONSERVATION DIVISION
Wichita, Kansas