


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stanton County, Sec. 26 Twp. 30S Rge. 41 NE/W
Location as "NE/CNW1SW1" or footage from lines
C NE/4

Lease Owner National Oil Company
Lease Name K.U. Endowment Well No. 1
Office Address Suite 550, Woo W. Douglas, Wichita, Ks 6720
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Locate well correctly on above
Section Plat

Date Well completed 4-8 1978
Application for plugging filed 4-8 1978
Application for plugging approved 4-8 1978
Plugging commenced 4-8 1978
Plugging completed 4-8 1978

Reason for abandonment of well or producing formation
no commercial quantities of oil or gas encountered
If a producing well is abandoned, date of last production
-- 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 5450
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface hole	shale	surf	1578	8-5/8	1570	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Fluid to 600', plug, 70 sx
Fluid to 40', plug, 10 sx
Rat hole 5 sx

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1978
4-14-1978
Conservation Division
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
515 R. H. Garvey Building
Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ella Priess (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Ella Priess
Suite 515, R.H. Garvey Bldg., Wichita, Ks. 6720
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of April, 1978

My commission expires 4/30/79

Dorothy L. Schmidt
Notary Public.

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1979

DRILLERS' LOG

NATIONAL OIL COMPANY
 No. 1 KU Endowment
 C NE/4 Sec 26-30S-41W
 Stanton Co., Ks.

Commenced: 3-29-78
 Completed: 4-8-78

Surface Casing: 1570' of 8-5/8" cmtd
 w/550 sx Lite Weight, 3% cc, 150 sx
 common, 3% cc. 3-30-78

FORMATIONDEPTH

Surface Hole	0 - 1578
Shale	1578 - 2020
Shale & Lime	2020 - 2284
Shale	2284 - 2564
Shale & Lime	2564 - 3116
Shale	3116 - 3326
Lime & Shale	3326 - 3755
Shale	3755 - 3973
Lime & Shale	3973 - 4161
Shale	4161 - 4321
Lime	4321 - 4471
Lime & Shale Streaks	4471 - 4614
Shale	4614 - 4848
Lime & Shale	4848 - 5058
Shale	5058 - 5190
Lime, Shale & Sand	5190 - 5340
Shale	5340 - 5450 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 10th day of April, 1978

Dorothy L. Schmidt
 Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
 STATE NOTARY PUBLIC
 Sedgwick County, Kansas
 My Appt. Exp. April 30, 1979