


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

McPherson County. Sec. 27 Twp. 20 Rge. (E) 3 (W)
Location as "NE/CNW%SW%" or footage from lines. SW/NW/NW
Lease Owner Jack Hinkle, et al
Lease Name J. C. Goering Well No. 1
Office Address 911 Union Nat'l. Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-4-19-56
Application for plugging filed 6-4-19-56
Application for plugging approved 6-4-19-56
Plugging commenced 6-4-19-56
Plugging completed 6-4-19-56
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruell Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3265 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	240'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 230' in heavy mud. Set bottom plugs with 1/2 sack hulls, and 15 sacks cement. Filled hole with mud to 30'. Set top plug at 30' with 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company
Address 607 Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
L. L. Bailey (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. L. Bailey
607 Union National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of June, 19 56

My commission expires August 20, 1956

Arthur R. Derrington
(Arthur R. Derrington) Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 27 T. 20 R 3w
BOOK PAGE 70 LINE 19

JUN 17 1956
CONSERVATION DIVISION
Wichita, Kansas
6-19-1956

WELL LOG

72068.

COMPANY **Jack Hinkle, et al**

SEC. 27 T. 20 R. 3-W

FARM **J. C. Goering**

NO. 1

LOC. **SW/WW/WW**

TOTAL DEPTH **3265'**


COMM. **5-24-56**

COMP. **6-3-56**

COUNTY **McPherson**
KANSAS

SHOT OR TREATED
CONTRACTOR **Lewis Drilling Company**

ISSUED



CASING

20	10
15	20 8 5/8" = 240'
12	6
13	5

ELEVATION **1475 RB.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 75	Clay & Sand
75 - 240	Shale & Shells
240 - 430	Shale
430 - 460	Anhydrite
460 - 550	Shale
550 - 2695	Shale & Lime
2695 - 2990	Lime
2990 - 3050	Lime & shale
3050 - 3130	Lime
3130 - 3190	Chert & Lime
3190 - 3210	Lime
3210 - 3265	Lime & shale
3265	T. D.

Geologic Tops:

Brown Line	2366'
Lansing	2416'
Marmaton	2966'
Mississippi	3046'
Kinderhook	3240'

PLUGGING
 FILE SEC 27 T 20 R 3W
 BOOK 70 LINE 19

RECORDED

State of KANSAS
 County of SEDGWICK } SS:

I, L. L. Bailey of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the J. C. Goering #1 well.

L. L. Bailey
(L. L. Bailey)

Subscribed and sworn to before me this 13th day of June 1956

My Commission Expires: August 20, 1956

Arthur R. Darrington
NOTARY PUBLIC
(Arthur R. Darrington)