15.113.01934.00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas


WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

NORTH



Locate well correctly on above Section Plat

McPherson County. Sec. 27 Twp. 20S Rge. (E) 3 (W)

Location as "NE¼NW¼SW¼" or footage from lines NW¼ NW¼ SW¼

Lease Owner The Aylward Production Company

Lease Name Stucky Well No. 6

Office Address 813 First National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed September 17 19 47

Application for plugging filed September 26 19 47

Application for plugging approved September 27 19 47

Plugging commenced September 28 19 47

Plugging completed October 2 19 47

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Siliceous Depth to top 3464 Bottom 3486 Total Depth of Well 3486 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	255'	None
				5 1/2"	3465'	2650'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Lane Wells plug set at 3455'. Perforated in 5½" in 3 sections or zones from 3445' up to 3357. No oil and plugging was started covering all perforations with cement from 3455' up 3350'. 5½" pulled out and hole filled with mud up to 250', bridged and 20 sacks cement at 250', filled with mud to the base of cellar and cemented with 5 sacks of cement.

11-25-1947

RECEIVED
NOV 25 1947

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Aylward Production Company

Address 813 First National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF ~~CEDAR~~ ELLSWORTH, ss.

Lewis Stoy (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lewis Stoy

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 19 47

Paul B. Hoffman
Notary Public.

My commission expires ~~February 25, 1950~~ Sept 30th 1949

21-871-s 9-45—6M

PLUGGING
FILE SEC 27 T 20 R 3W
BOOK PAGE 135 LINE 40

15.113 01934.00.00

STUCKY NO. 6

Casing Record:
8-5/8" - 250'
5½" -3465'

Company: The Aylward Production Company
Contractor: Aylward Drilling Company

Commenced: August 20, 1947
Completed: September 17, 1947

Location:
NW¼ NW¼ SW¼ of Sec. 27-20S-3W, McPherson County, Kansas
Elevation:
Potential: D & A

Formation	From	To	Remarks
Surface Clay	0	35	
Sand	35	85	
Shale	85	105	
Shale & Shells	105	250	Set 8 5/8" Casing @ 250'
Shale	250	385	Cemented with 125 Sacks
Shale & Shells	385	450	
Shale & Broken Lime	450	615	
Lime & Shale	615	720	
Sand	720	740	
Lime	740	830	
Lime & Shale	830	1215	
Shale	1215	1627	
Shale & Lime	1627	1775	
Shale	1775	1845	
Lime & Shale	1845	1935	
Shale	1935	1995	
Lime & Shale	1995	2050	
Shale	2050	2087	
Shale & Lime	2087	2726	
Lime	2726	2865	
Lime & Shale	2865	2950	
Shale	2950	2985	
Chat	2985	3080	
Shale & Lime	3080	3210	
Shale	3210	3330	
Shale & Sand	3330	3359	
Lime & Shale	3359	3422	
Shale & Sand	3422	3458	
Lime	3458	3486	5½" Casing set @ 3465'. Cemented w/200 sax. Set Lane Well Plug @ 3445'
			24 shots from 3436-44
			15 " " 3421-26
			15 " " 3451-62

3486 T. D.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

J. C. Stalcup

Subscribed and Sworn to before me this 26th day of September, 1947.

G. B. Dixon
Notary Public

My commission expires February 25, 1950.

PLUGGING
FILE SEC 27 T 20 R 3W
BOOK PAGE 135 LINE 40