


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
11 No. Broadway  
Wichita, Kansas

Kiowa County, Sec. 1 Twp. 30S Rge. (E) 17 (W)

Location as "NE/CNW%SW%" or footage from lines C SE SE  
Lease Owner Pickrell Drilling Company  
Lease Name Rice Well No. 1-1  
Office Address 705 Fourth National Bank Bldg. - Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 27, 19 62  
Application for plugging filed July 27, 19 62  
Application for plugging approved July 27, 19 62  
Plugging commenced July 27, 19 62  
Plugging completed July 27, 19 62  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. LacKamp  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4971 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	322'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 261'. Set Plug. Cemented with  
25 sacks cement. Heavy mud to 30'. Set Plug.  
Cemented with 15 sacks cement to bottom of  
cellar. Plugged rat hole with 2 sacks cement.

8-1-62

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 1 1962  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Bldg. - Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. W. SEBITS (Agent, Owner or Operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) C. W. Sebits  
705 Fourth National Bank Bldg. - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of August, 19 62  
Maxine Blackman  
Maxine Blackman Notary Public.

My commission expires June 21, 1966

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Bldg.  
Wichita 2, Kansas

Rotary Drilling Commenced 7-12-62

Rotary Drilling Completed 7-27-62

LOCATION: Rice #1-1 - C SE SE  
Sec. 1-30S-17W - Kiowa County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY  
Wichita, Kansas

CASING RECORD: (16 jts) 8 5/8" Surface Casing set at 322', cemented with 200 sacks  
cement. Circulated. Completed 7:30 P.M. 7-12-62.  
No oil string run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>Circulated for samples</u>	
130	Blue Shale		
200	Shale & shells	4780'	4856'
300	Red Rock	4790'	4882'
322	Anhydrite	4815'	4907'
815	Red Rock & clays	4836'	4971'
895	Anhydrite & Red Rock		
1560	Red rock & shale		
1910	Shale & shells		
2200	Shale, shells & Lime		
2720	Lime		
3950	Lime & Shale		
4606	Lime	1000'	0°
4665	Lime & Shale	1700'	0°
4709	Lime	2500'	0°
4761	Lime & Shale	3400'	0°
4800	Lime, sand & Shale	4800'	0°
4826	Lime		
4951	Mississippian		
4961	Kinderhook		
4971	Viola R.T.D.		

Slope Test

1000'	0°
1700'	0°
2500'	0°
3400'	0°
4800'	0°

S. L. M.

3215'
3855'
4335'
4709'

RECEIVED  
STATE CORPORATION COMMISSION

AUG 15 1962

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS

COUNTY OF SEDGWICK } ss.:

On this 10th day of August, 19 62, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. SEBITTS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman  
Maxine Blackman Notary Public