

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County, Sec. 5 Twp. 30S Rge. 17W E 7W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines

2310' FWL & 1320' FNL
Lease Owner Texas Oil & Gas Corp.

Lease Name Kane Well No. 1

Office Address 200 W. Douglas, Suite 300, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202

Dry Hole

Date Well completed October 31, 1978

Application for plugging filed Verbal Application 19

Application for plugging approved Verbal Approval 19

Plugging commenced October 31, 1978

Plugging completed October 31, 1978

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 4,932'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	450'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 4,932 ft. (rotary total depth) to 450 ft. Set plug at 450 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 450 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Allied Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.
Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Dean Britting

200 N. Main, Wichita, KS 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of November, 1978

Elsie Willison
Elsie Willison - Notary Public.


My commission expires July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1978

11-13-78

CONSERVATION DIVISION
Wichita, Kansas



KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.

SEC. 5 T. 308 R. 17W
LOC. 2310' PWL & 1320' FNI

FARM Kane NO. 1

COUNTY Kiowa

ROTARY TOTAL DEPTH 4,932'
COMM. October 19, 1978 COMP. October 31, 1978
CONTRACTOR H-30, Inc. (Rig #3)
ISSUED November 10, 1978

CASING

10 3/4"
8 5/8" Set at 450' cemented w/400 sxs cement
5 1/2"
4 1/2"

ELEVATION 2,095' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	996'
Shale and Lime	2,215'
Lime and Shale	2,464'
Shale and Lime	2,469'
Lime and Shale	3,000'
Shale and Lime	3,198'
Lime and Shale	3,508'
Shale and Lime	4,030'
Lime and Shale	4,631'
Shale, Lime and Chert	4,746'
Lime and Shale	4,882'
Lime	4,932'
Rotary Total Depth	4,932'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } SS:

Subscribed and Sworn to before me a Notary Public in and foresaid county and state this 10th day of November, 1978.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

NOV 13 1978

CONSERVATION DIVISION
Wichita, Kansas