


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW%SW%" or footage from lines KIOWA County. Sec. 29 Twp. 30S Rge. 17 (X) (W)  
APP. C WEST LINE  
Lease Owner PETROLEUM, INC.,  
Lease Name BOOTH UNIT Well No. C-1  
Office Address R.R. #2, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed JANUARY 19 19 69  
Application for plugging filed JANUARY 19 19 69  
Application for plugging approved JANUARY 19 19 69  
Plugging commenced JANUARY 19 19 69  
Plugging completed JANUARY 19 19 69  
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE

If a producing well is abandoned, date of last production NONE 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well R. J. WARREN  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5081 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1002'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

HEAVY MUD TO 300', FOLLOWED BY WOODEN PLUG, PLACED 25 SACKS CEMENT ON TOP OF PLUG. HEAVY MUD TO 40', FOLLOWED BY WOODEN PLUG, 1/2 SACK HULLS, BRIDGE TO HOLD KELLY, 10 SACKS CEMENT TO BASE OF WELL CELLAR.

1-29-1969  
RECEIVED  
STATE CORPORATION COMMISSION  
JAN 29 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor GARVEY DRILLING COMPANY  
Address R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
MONTE CHADD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Monte Chadd  
R.R. #2, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 27 day of JANUARY, 19 69


Richard H. Dumbler  
Notary Public.

My commission expires MAY 28, 1969

# WELL LOG

COMPANY Petroleum, Inc. SEC. 29 T. 30S R. 17W  
 FARM Booth Unit NO. C-1 LOC. C/W Line  
 TOTAL DEPTH 5081' COUNTY Kiowa Co., Kansas  
 COMM. 1-5-69 COMP. 1-19-69  
 CONTRACTOR Garvey Drilling Company

CASING 8 5/8" @ 1002' w/600. sx



ELEVATION 2136' KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 40' Clay & Sand
- 270' Sand & Shale
- 410' Red Bed
- 422' Red Bed & Anhydrite
- 440' Anhydrite
- 1000' Red Bed & Shale
- 1010' Shale
- 1202' Shale & Shells
- 2030' Shale
- 2555' Lime & Shale
- 2642' Lime
- 3835' Lime & Shale
- 4180' Lime
- 4445' Lime & Shale
- 4770' Lime
- 4830' Lime & Shale
- 4925' Lime
- 5011' Shale & Chert
- 5031' Lime & Chert
- 5081' Lime & Shale
- 5081' RTD

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 29 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

State of Kansas }  
 County of Barton } ss

I, Eunice McEachern of Garvey Drilling Company  
 upon oath state the above and foregoing is a true and correct copy of the log of the Booth Unit C-1 well.

Eunice McEachern

Subscribed and sworn to before me this 24th day of January 19 69

My Commission Expires: November 5th, 1969

Richard D. Doy  
 NOTARY PUBLIC