

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

15.097-20436-0001  
Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Kiowa SEC. 30 TWP. 30s RGE. 17w E/W  
Location as in quarters or footage from lines:  
C of SW $\frac{1}{4}$


Locate Well  
correctly on above  
Section Platt.

Lease Owner Beren Corporation  
Lease Name Snyder #2 Well No. \_\_\_\_\_  
Office Address 970 Fourth Financial Center, Wichita, Ks 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 4/21/83  
Plugging completed 4/26/83  
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 5104'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	554'	none
				4 1/2"	5038'	3622'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Squeezed 4 1/2" casing with 1 sack hulls, & 50 sacks common cement 2% gel.  
Pumped plug to 4400'. Shot casing at 4000' & 3620'. Pulled total of 84 joints. Squeezed hole with 3 hulls, 15 gel, 70 cement, 10 gel, & 1 hull.  
Released plug & displaced with 150 cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 83

My Commission expires:



Irene Hoover  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION  
5-6-1983  
MAY 06 1983

CONSERVATION DIVISION  
Wichita, Kansas

15-097-20436-0001

## (P) RILLERS LOG

SNYDER #2 (OWWO)

C SW

Sec. 30-30S-17W

Kiowa County, Kansas

Company: Beren Corporation

Contractor: BEREDCO INC.

Comm: 6/6/81

Comp.: 6/8/81

Casing: 4 1/2", 10.5# set at 5138' with 250 sacks 60-40 Pozmix, 2% gel, 10% salt  
gilsonite per sack 3/4% CFR2

FORMATION

FROM

TO

No formations available (OWWO)

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

I certify that this is a true and correct copy of the above log as  
shown by the drilling reports.

BEREDCO

Subscribed and sworn to before me this 19th day of June, 1981.

MARICA J. DEARTH  
State of Kansas  
My Appt. Exp. Apr. 27, 1982

THE MAURICE L. BROWN CO.

200 SUTTON PLACE

WICHITA, KS.

CONTR ABERCROMBIE DRG., INC. CTY KIOWA

#1 WATERS

30-30-17W

C SW/4

GEOL FIELD WC (3/4 SW OF GLICK)

E 2157 KB CM 12/13/77 CARD  
ISSUED 1/19/78 IF D&A/MISS  
12/30/77

API 15-097-20,436

LOG	TOPS	DEPTH	DATUM
IND CV	3316	-1159	
HEEB	4210	-2053	
TOR	4224	-2067	
BR LM	4372	-2215	
LANS	4388	-2231	
BKC	4802	-2645	
MARM	4813	-2656	
CHER	4947	-2790	
REW MISS	5016	-2859	
MISS (SPERG-WAR)	5024	-2867	
MISS (QS)	5065	-2900	
TD	5104	-2947	

8-5/8" 554/450sx  
DST (1) 4801-4837/60-60-60-90, 30' WDM,  
SIP 57-57#, FP 32-32#, 32-32#  
DST (2) 4849-4890/60-60-60-90, 30' WDM  
SIP 69-65#, FP 48-57#, 57-57#  
DST (3) 4997-5027/60-60-60-90, 20' DM,  
SIP 59-59#, FP 39-39#, 39-39#  
DST (4) 5038-5044/60-60-90-120, GTS/35"  
STAB @ 19 MCFG, 90' HOCM, 30' MO,  
SIP 1623-1584#, FP 39-39#, 39-39#  
DST (5) 5044-5064/60-60-90-120, GTS/3"  
STAB @ 6 MCFG, 90' HO&GCM, 30' MO,  
SIP 1565-1623#, FP 20-49#, 49-69#  
DST (6) 5076-5089 (W/SP)/60-60-60-90  
190' SW, SIP 1291-1291#, FP 10-79#  
79-98#

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

RECEIVED  
STATE CORPORATION COMMISSION

FEB 7 1983

CONSERVATION DIVISION  
Wichita, Kansas