

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-097-21,264-0000

LEASE NAME BOOTH

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

2300 Ft. from S Section Line

3580 Ft. from E Section Line

SEC. 34 TWP. 30S RGE. 17 ~~05~~ or (W)

COUNTY Kiowa

Date Well Completed _____

Plugging Commenced Aug. 6, 1990

Plugging Completed Aug. 9, 1990

LEASE OPERATOR CLUTE OIL CORP.

ADDRESS 444 17th Street, #608 Denver, Co. 80202

PHONE#(303 623-6779) OPERATORS LICENSE NO. 30160

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 7, 1990 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5200
 Perfs: 4998-5012 and 5016-28 ~~FBTP~~ 5112

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	465	8 5/8	465	0
			5152	4 1/2	5152	3710'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Aug. 6, 1990: To location, rigged up. 8-7-90, got free point and shot off and pulled 3710 ft. of 4 1/2" casing. First dumped sand to 50' above top perfs, and dumped 4 sx. cement on top of the sand. Aug 9, 1990: Allied Cement pumped 300# hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, 100# hulls, 150sx. cement, 60 40 poz, 6% gel. 8-14-90, dumped sand mix cement to top.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P.O. Box 847 Pratt, Kansas 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CLUTE OIL CORP. 8-16-90

STATE OF KANSAS COUNTY OF PRATT, ss. Wichita, Kansas


JUDY BERRY

(Employee of ~~Operator~~)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed thereon, and the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) _____



SUBSCRIBED AND SWORN TO before me this 14th day of August, 19 90

Dorothy M. Ferguson
 Notary Public

My Commission Expires February 6, 1993