

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-097-21,276-0000

LEASE NAME Cromer

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

600 Ft. from S Section Line

800 Ft. from E Section Line

SEC. 34 TWP. 30S RGE. 17 (X or W)

COUNTY Kiowa

Date Well Completed _____

Plugging Commenced Aug. 2, 1990

Plugging Completed Aug. 9, 1990

LEASE OPERATOR Clute Oil Corp.

ADDRESS 444 17th Street, #608 Denver, Co. 80202

PHONE# (303) 623-6779 OPERATORS LICENSE NO. 30160

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 7, 1990 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5040

Perfs: 5000-06 and 5014-5020.

Plug back TD 5038

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	463	8 5/8	463	0
			5038	4 1/2	5038	2578'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
8-2-90: Rigged up, pulled 160x3/4 rods and 38x 7/8 rods and 155 jts of 2 3/8" tubing, dumped sand to 50' above top perfs, plus 4 sx. cement. 8-6-90, cut at free point and pulled 2578' of 4 1/2 casing. 8-9-90: Allied Cement pumped 300# hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, 100# hulls, 150sx. cement, 60 40 noz and 6% gel. On 8-14-90, filled to top with sand mix cement.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address Box 847 Pratt, Ks. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Clute Oil Corp.

AUG 16 1990 8-16-90

STATE OF Kansas COUNTY OF Pratt


Judy Berry

CONSERVATION DIVISION
 EMPLOYEE OF PLUGGING CONTRACTOR
 (Employee's Name, Address, City, State, Zip Code) XXXXX

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed thereon, and the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) _____



SUBSCRIBED AND SWORN TO before me this 14th day of August, 19 90

Dorothy M. Ferguson
 Notary Public

My Commission Expires: February 6, 1993