

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kiowa County. Sec. 1 Twp. 30S Rge. 18W (E) (W)

Location as "NE/CNW%SW%" or footage from lines C S/2 SE/4

Lease Owner K & E Drilling, Inc.

Lease Name Nichols Well No. 1

Office Address 719 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 12/18 19 66

Application for plugging filed 12/18 19 66

Application for plugging approved 12/18 19 66

Plugging commenced 12/18 19 66

Plugging completed 12/18 19 66

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Elving, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4959 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	462'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud up to 275'. Solid bridge w/1/2 sx. hulls & plug.
Spotted 25 sx. cement above plug. Heavy mud to 40'. Solid
bridge w/1/2sx. hulls and plug. Spotted 10 sx. cement above plug.
Plugging completed at 1:30 A.M.

12-23-66
RECEIVED
DEC 23 1966
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.

Address 719 Union Center Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wayne L. Brinegar (employee of owner) or (XXXXXXXXXX) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne L. Brinegar Wayne L. Brinegar

719 Union Center, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of December, 1966

My commission expires 9-14-70

Judie K. Eby Notary Public.



DRILLER'S WELL LOG

OPERATOR: K & E DRILLING, INC.
719 Union Center Building
Wichita, Kansas 67202

WELL NAME: #1 Nichols
LOCATION: 100' West & 50' South of
C S/2 SE/4 Sec. 1-30S-18W
Kiowa County, Kansas

CONTRACTOR: **K&E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

CASING RECORD:
8-5/8" @ 462' w/275 sx.

COMMENCED: 12/4/66
COMPLETED: 12/18/66
ELEVATION: 2110' Gr; 2116' DF;
2119' KB
PRODUCTION: Dry

ROTARY TOTAL DEPTH: 4959'

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Clay & Soil	70
Shale	385
Sand	425
Anhydrite	460
Shale & Shells	2055
Shale & Lime	2275
Lime	2420
Lime & Shale	2629
Lime	2875
Lime & Shale	2997
Lime	3155
Lime & Shale	3445
Lime	4940
Kelly Corr.	4940-4942
Chert	4959

RECEIVED
OIL & GAS COMMISSION
DEC 23 1966
REGISTRATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, Wayne L. Brinegar, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Wayne L. Brinegar
Wayne L. Brinegar

Subscribed and sworn to before me this 22nd day of December 1966.

Judie K. Eby
Judie K. Eby Notary Public.

My Commission expires: 9-14-70

