

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 10 1964
2-10-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Alfred Koehn

Complete Address: Galva, Kansas

Lease Name Goering Well No. 1

Location NE NE NW Sec. 27 Twp. 20 Rge. 3 (E)X (W)

County McPherson Total Depth 3130'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Art Lamb Casing Pulling Co.

Address: P.O. Box 983, Hutchinson, Kansas License No. 440

Operation Completed: Hour 2:30PM Day 6 Month 2 Year 64

The Above well was plugged as follows:

Filled hole w/ sand from T.D. 3130' back to 2995', Ran 5 sax cement w/ dump bailer.
Shot off and pulled 6" casing. Filled hole w/ mud from 2960' back to 170'. Set a 10'
rock bridge and ran 20 sax cement from 160' back to 90'. Filled hole w/ mud from 90'
back to 30' set a 5' rock bridge and ran 8 sax cement from 25' back to zero 3' below
ground level. 8 5/8" surface pipe 3' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Frederick J. Jones
Well Plugging Supervisor

DATE 2/11/64

INV. NO. 8604-11