


Form CP-3
Rev. 6-26-62

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed March 1, 1967.

MAR 20 1967

3-20-67

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas

Lease Name Kane Unit Well No. # 1

Location App. C SW Sec. 8 Twp. 30 Rge. 17 (E) (W) W

County Kiowa Total Depth 4845'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No.

Operation Completed: Hour 10:00PM Day 17th Month March Year 1967

The Above well was plugged as follows:

506' of 8 5/8" surface pipe, cement circulated with 400 sacks. Hole
was filled with drilling mud to 400', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 400', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at
40', and cemented with 9 sacks to the base of the cellar. Rat and mouse
holes bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/20/67
INV. NO. 4923-W

Signed: Audie Elving
Well Plugging Supervisor