

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-097 20,442 (?)

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Petroleum Service

Complete Address Suite 800 R.H. Loney Bldg. 300 West Douglas Wichita, Kans. 67202

Lease Name Ranton Well No. C-2

Location 1250'SNL-1620'W.E.L. NE Sec. 20 Twp. 30 Rge. 17 (East) (West)

County Kiowa Total Depth 5015'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Clark Corporation

Address 107 West Fowler Medicine Lodge Kans License No. 583

Operation Completed: Hour: 12:00 AM. Day: 14 Month: July Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They ran 5013' of 5 1/2" production pipe & plugged it back to 4937'. Then they perforated it from 4808' to 15'. 1st plug sandbed off bottom back to 4780' & dumped 5 bbls of cement on top of it. 2nd plug pumped thru 8 3/8" head 5 bbls shells 25 bbls gell & released rubber plug and followed it with 150 bbls of cement. The cement used was common with 2% gell & 3% CC. They had recovered 3400' of 4 1/2" pipe. The plugging was accomplished by sum cementing. Shut in pressure 500 lbs. Amount of Surface Casing: 518' of 8 1/2" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthis
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
7-20-82
JUL 20 1982
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 7-22-82
INV. NO. 669-41

