

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1972
CONSERVATION DIVISION
Wichita, Kansas
7-14-72J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Fender Pipe & Supply Inc.

Complete Address Box 302 Russell, Ks

Lease Name Booth C Well No. 1

Location C E/2 NE Sec. 29 Twp. 30 Rge. 17 (E) (W) W

County Kiowa Total Depth 5138

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Cassing & Pulling Co Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 3:00 PM Day 12 Month 7 Year 1972

The above well was plugged as follows:

408 ft 9 5/8 surface pipe cemented with 500 sacks. 5138 ft 4 1/2 long

string cemented with 125 sacks. Top perf. 5006 ft. Sand to 5000 ft,

3 sacks cement with bailer. Pulled 3600 ft 4 1/2. Set 10 ft rock bridge

at 250 ft, 25 sacks cement. Bridge at 40 ft with 10 sacks cement

to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE

7/14/72

INV. NO.

6029-W