

¹⁰ KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 2 - 1965

8-2-65

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name K & E Drilling, Inc.

Complete Address: 719 Union Center Bldg., Wichita, Kansas

Lease Name Frank Nichols Well No. # 1

Location 150' S of C E/2 SW Sec. 1 Twp. 30 Rge. 18 (E) (W) W

County Kiowa Total Depth 5060'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: K & E Drilling, Inc.

Address: 719 Union Center, Wichita, Kansas License No.

Operation Completed: Hour 12:15AM Day 30th Month July Year 1965

The Above well was plugged as follows:

432' of 8 5/8" surface pipe, cemented with 375 sacks. Hole was filled
with drilling mud to 300', 1st cementing plug, bridged solid with dry
cement and hulls on fluid at 300', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with dry cement and hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8/2/65
INV. NO. 1556-W