

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

A 4x4 grid of squares. The top-left square is shaded gray. The other squares are white.

**Locate well correctly on above
Section Plat**

800 Bittling Building
Wichita, Kansas

McPherson County, Sec. 13 Twp. 19 Rge. 3 (25) (W)

NORTH

Locate well correctly on above
Section Plat

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines CW/2 E/2 SE

Lease Owner Kantor Oil Company

Lease Name Chindberg Well No. 3

Office Address P. O. Box 846, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed February 18, 19 16

Application for plugging filed August 16, 19 51

Application for plugging approved August 17, 19 51

Plugging commenced November 6, 19 51

Plugging completed November 13, 19 51

Reason for abandonment of well or producing formation
Oil not in paying quantities

If a producing well is abandoned, date of last production _____ 19 ____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee

Producing formation Mississippi Depth to top 2982 Bottom 3032 Total Depth of Well 3032 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Dumped 6 sacks of cement at bottom of hole. Filled back with sand to 2990'. Shot pipe off at 2356'. Pulled pipe and mudded hole to 190'. Set rock bridge and dumped 15 sacks of cement. Finished mudding hole and dumped 5 sacks of cement at top of surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... Kantor Oil Company
Address..... Box 816
..... Tulsa, Oklahoma

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.

.....(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God. *[Signature]*

(Signature)

Tulsa. Okla.

(Address)

SUBSCRIBED AND SWORN to before me this 19th day of November, 1957

My commission expires January 11, 1952

23-3273-S

4-50-10M

STATE OF

NOV 20 1951

CONGRESSIONAL DIVISION
Wichita, Kansas

FORMATIONS ENCOUNTERED IN DRILLING OF

CHINDBERG WELL NO. 3

CW/2 E/2 SE, Sec. 13-19-3W

McPHERSON COUNTY, KANSAS

Total Depth 3032'

Comm. 2-2-46

Comp. 2-18-46

Casing:

8-5/8" 204'

5-1/2" 3000'

Figures Indicate Bottom of Formation

soil	0-60
sand	95
red bed & shale	165
shale blue	208
shale	450
lime & shale	580
shale & shells	800
lime & shale	970
shale & shells	1050
lime	1145
lime & shale	1305
shale & shells	1410
lime & shale	1800
shale	1835
lime & shale	1845
lime	1895
lime & shale	1920
shale	1950
lime & shale	2025
lime	2065
lime & shale	2260
lime	2320
shale	2355
lime & shale	2405
lime	2480
lime & shale	2545
lime	2580
lime & shale	2960
shale	3003
lime	3032
Total Depth	

13-19-3W
104-13

NOV 20 1951
CONSERVATION DIVISION
Wichita, Kansas