

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required at
Mail or Deliver to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

McPherson County, Sec. 13 Twp. 19S Rge. 5 (W)

Location as "NE/CNW/SW" or footage from lines NW NE NW

Lease Owner Johnson Bro's., Bauer & Fredricks

Lease Name M. R. Seidel Well No. 1

Office Address 123 E. 3rd., Mitchell, S. D.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed December 6, 19 53

Application for plugging filed " 6, 19 53

Application for plugging approved " 6, 19 53

Plugging commenced 5 P.M. " 6, 19 53

Plugging completed 9 P.M. " 6, 19 53

Reason for abandonment of well or producing formation Non Productive

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, McPherson, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3338 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	715	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 185-135 feet to 20-7 feet for each plug set.

Guned pits, circulated heavy mud on bottom, layed/half of drill pipe circulated heavy mud. Layed down all but 185' of drill pipe, made bridge out of limbs and top Halliburton plug, then rock to hold weight of drill pipe. Mixed 15 sacks cement and put thru 6 joints drill pipe, run measuring line and filled to 20 feet with heavy mud, made bridge there mixed 5 sacks cement and put on there to fill to bottom of cellar. Through plugging @ 9:00 P.M., December 6, 1953.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E. K. Carey Contractor

Address Box 620, McPherson, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss. Arland Bruce (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arland Bruce

12-6-53 McPherson Kas. (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 53

My commission expires November 13, 1956 Notary Public.

PLUGGING
FILE SEC 13 T 19 R 50
BOOK PAGE 147 LINE 31

24-2675-S 2-52-20M

12-8-53

ROTARY DRILLERS' LOG

Johnson Bros', Bauer & Fredricks
123 E 3rd Avenue
Mitchell, South Dakota

Elevation: 1519 K.B.
1516 D.F.
1513 Gr.L.

Seidel #1

C, NW NE NW/4
Sec. 13-19S-5W
McPherson County, Kansas

Casing Record:
8-5/8" @ 715' w/250 sks.
of Pozmix and 200 sacks of
Reg. Bulk Cement and 400# cc.

Well Commenced: 11-23-53
Well Completed: 12-6-53

Contractor: E. K. Carey Contractor, Rig #2, Box 620, McPherson, Kansas
Geologist: Donald H. Smith, 5206 E. Central, Wichita, Kansas

Figures Indicate Bottom of Formation K. B.

Cellar	7
Shale	60
Shale & shells	430
Salt & shale	665
Shale	685
Anhydrite	715
Lime & shale	1235
Shale & lime	1310
Lime & shale	1500
Shale & lime	1590
Shale	1765
Shale & lime	2050
Lime & shale	2120
Shale & lime	2170
Lime	2315
Lime & shale	2525
Shale & lime	2635
Shale	2660
Lime	3035
Lime & shale	3195
Shale & shells	3255
Shale	3288
Lime	3338 TD

Geologist Tops:

Hebner	2432 (- 913)
Br. Lime	2508 (-1069)
Lansing-Kansas City	2657 (-1138)
Base Kansas City	3038 (-1519)
Marmaton	3043 (-1524)
Cherokee	3171 (-1652)
Congl.	3264 (-1745)
Mississippi	3287 (-1768)
Total Depth	3338 (-1819)

This is to certify that the above information is to the best of my knowledge true and correct.

SUBSCRIBED AND SWORN to before me this 7th day of December, 1953.

E. K. CAREY CONTRACTOR

BY Herbert Rhoton
Herbert Rhoton, Superintendent

[Signature]
NF

My Commission Expires: November 13, 1956.

