


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail Deliver Report to:
Conservation Division
State Corporation Commission
Printing Building
Wichita, Kansas

McPherson County, Sec. 6 Twp. 19S Rge. (E) 5 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines SW NW SW
Lease Owner Trans-Era Petroleum, Inc.
Lease Name Harter Well No. 1
Office Address 420 West Douglas, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 10-22 19 55
Application for plugging filed 10-22 19 55
Application for plugging approved 10-22 19 55
Plugging commenced 10-22 19 55
Plugging completed 10-22 19 55
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale		0	177	8-5/8"	177	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top _____ feet to bottom _____ feet for each plug set.

Mud to 177' - Halliburton Plug - 1/2 sack hulls
15 sacks cement thru drill pipe
147' to 40' mud
At 40' Halliburton Plug - 1/2 sack hulls
5 Sacks Cement to Cellar - Zero

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Trans-Era Petroleum, Inc.
Address 420 West Douglas, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
I, C. R. Hamzavi, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Hamzavi
420 West Douglas, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 55

My commission expires August 2, 1958 Notary Public.

PLUGGING
FILE NO. 67.19.50
BOOK PAGE 10 LINE 24

11-15-55

HARTER #1

SW NW SW

Section 6-19S-5W

McPherson County, Kansas

Trans-Era Petroleum, Inc.

Commenced: October 4, 1955

Completed: October 22, 1955

Casing Record: Set 177" 8-5/8" with 125 sacks cement.


<u>FORMATION</u>	<u>DEPTH</u>
Clay - Sand - Shale	100
Shale	177
Shaled Red Bed	350
Shale - Lime - Shale	925
Shale - Sandy Lime	1075
Shale - Lime	1385
Lime - Shale	1510
Shale - Lime	1870
Shale	2000
Shale - Lime	2560
Lime	2614
Shale - Lime	2662
Lime - Shale	2725
Lime	2785
Lime - Shale	2935
Lime	3123
Lime - Shale	3190
Lime	3250
Lime - Shale	3404
Lime	3452
Lime - Shale	3491
Lime	3541
Cherty Lime	3566
Lime - Chert	3591
Lime	3620
Lime - Shale	3670
Shale - Lime	3778
Lime - Shale	3845
Shale - Lime	3870
Lime - Shale	3897
Lime	3912
Shale - Lime	3935
Lime - Sand	3961
Lime - Shale	3981
Arbuckle	4003
ROTARY TOTAL DEPTH	4003

STATE OF KANSAS)
) ss.
 COUNTY OF SEDGWICK)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. R. Hansen

Subscribed and sworn to before me this 28th day of October, 1955.



My Commission Expires August 2, 1958

