

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NOT ASSIGNED

LEASE NAME BENDER

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 1 TWP. 23S RGE. 18 ~~XXXX~~(W)
SW SW SW

LEASE OPERATOR HINKLE OIL COMPANY

ADDRESS 1016 UNION CENTER BLDG. WICHITA, KS. 67202

COUNTY PAWNEE

PHONE#(316) 267-0231 OPERATORS LICENSE NO. 5290

Date Well Completed _____

Character of Well GAS

Plugging Commenced 6-8-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-10-93

The plugging proposal was approved on JUNE 10, 1993 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation _____ Depth to Top PBTD:4526
~~XXXXXXX~~ T.D. 4555

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	215	8 5/8	215	0
		0	4547	4 1/2	4547	2610 FT.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

DUMPED SAND AND FOUR SACKS OF CEMENT TO COVER TO 50FT. ABOVE TOP PERES. 6-11-93: ALLIED CEMENT TOP HOLE PLUGGED WITH 300# OF HULLS, 10 SX. GEL, 50 SX. CEMENT, 10 SX. GEL, 100# HULLS 8 5/8 PLUG, 150 SX. CEMENT. 60 40 POZ, 6% GEL: 700# MAX, 150# IS IP. 6-14-93: TOP OF CEMENT DOWN THREE FEET FROM THE SURFACE

(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KS. 67124.

JUN 18 1993
6-18-93


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: HINKLE OIL CO. CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY (Employee of ~~XXXXXXXXXXXXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) P W S, INC. Judy Berry

(Address) P.O. Box 847 - Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 16th day of June, 19 93

Dorothy M. Ferguson
Notary Public

My Commission Expires: February 6, 1997