


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

Pawnee County, Sec. 35 Twp. 23 Rge. 18 (X) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW&SW" or footage from lines SW SW SW
Lease Owner Welch & Olsson Drilling Co. Inc.
Lease Name Bender Well No. 1
Office Address 203 Rule Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 2-9 19 55
Application for plugging filed 2-9 19 55
Application for plugging approved 2-10 19 55
Plugging commenced 2-10 19 55
Plugging completed 2-10 19 55
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner, Box 207, Great Bend, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded to 200'. Set 8 5/8 bottom hole plug. Used one-half sack of hulls and cemented with 20 sacks of cement. Bottom plug set at 35'. Used 30 sacks of hulls; cemented with ten sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Welch & Olsson Drilling Co. Inc.
Address 203 Rule Bldg., Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. E. Welch (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

203 Rule Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of February, 19 55

My commission expires June 12, 1955

[Signature] Notary Public.

PLUGGING
FILE SEC 35 T 23 R 18
BOOK PAGE 96 LINE 44

2-23-55

WELL LOG.

WELCH & OLSSON DRILLING COMPANY, INC.

ELEVATION: 2133 R.B.

CONTRACTOR: Welch & Olsson Drlg. Co. Inc.

Comm. Drlg: 1-19-55

BENDER #1
SW SW SW 35-23-18W
Pawnee County, Kansas.

Compl. Drlg: 2-9-55

Production: D & A

Casing Record:
215' of 8 5/8" with 150 sacks of cement.

(Figures indicate bottom of Formations.)

<u>FORMATIONS:</u>	<u>DEPTHS</u>	<u>FORMATION TOPS.</u>	
Sand & Shale:	215	Heebner:	3754 (-1621)
Red Bed & Shale:	675	Brown Lime:	3865 (-1732)
Sand:	720	Lansing-Kansas City:	3873 (-1740)
Shale:	970	Conglomerate:	4329 (-2196)
Red Bed & Shale:	1185	Mississippi (Chert):	4405 (-2272)
Anhydrite:	1210	Kinderhook (Misener) Sand:	4478 (-2345)
Shale & Shells:	2005	Viola:	4510 (-2377)
Shale & Lime:	3170		
Shale & Shells:	3250		
Shale W/Lime str:	3270		
Shale & Lime:	3450		
Lime:	3794		
Lime & Shale:	3860		
Lime:	4329		
Conglomerate:	4406		
Lime:	4487		
Sand:	4488		
Lime:	4545 T.D.		

STATE OF KANSAS)
) SS:
SEDGWICK COUNTY)

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the SW SW SW of Section 35, Township 23 South, Range 18 West, Pawnee County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.

BY R. E. Welch
R. E. WELCH

Subscribed and sworn to before me this 17th day of February, 1955

Seal Shaw
Notary Public.

My commission expires:
June 12, 1955

