


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stanton County. Sec. 15 Twp. 30S Rge. 41W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW
Lease Owner Musgrove Drilling Company
Lease Name DICKEY Well No. 1
Office Address 801 Union Center, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 4-26-61 19
Application for plugging filed verbally - 4-25-61 19
Application for plugging approved verbally - 4-25-61 19
Plugging commenced 4-26-61 19
Plugging completed 4-26-61 19
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 5581' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1589'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 1500'.
Set 1st plug at 1500' w/15 sx cement
Filled hole w/heavy mud to 400'.
Set 2nd plug at 400' w/ 25 sx cement.
Mud to 35'.
Capped w/10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 4 1961 5-4-61

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Wardco Drilling Company, Inc.
Address West Tenth Street, Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Emil E. Bowers (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 1961

Leah Faye Hefke
Leah Faye Hefke Notary Public.

My commission expires June 16, 1963



CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Drilling Company
CONTRACTOR:	Wardco Drilling Company, Inc.
FARM:	DICKEY #1
LOCATION:	C SW Sec. 15-30S-41W Stanton County, Kansas
COMMENCED:	March 30, 1961
COMPLETED:	April 26, 1961

0	510	Surface clay
510	865	Red bed
865	1010	Shale, Anhydrite, shells
1010	1144	Sand, shale, anhydrite
1144	1207	Anhydrite, sand
1207	1210	Sand, anhydrite
1210	1250	Sand, shale
1250	1414	Shale, sand, anhydrite
1414	1585	Shale, sand
1585	1560	Anhydrite
1600	1644	Shale
1644	1920	Shale, shells, anhydrite
1920	2017	shale
2017	2110	Shale, lime
2110	2290	Shale, shells, limestreaks
2290	4090	Lime, shale
4090	4149	Lime
4149	4319	Lime, shale
4319	4408	Lime, shale, sand
4408	4442	Lime, shale
4442	4514	Lime
4514	5273	Lime, shale
5273	5298	Lime, sand, shale
5298	5333	Lime, shale
5333	5401	Lime
5401	5431	Mississippi lime
5431	5581	Lime
5581		Rotary Total Depth

Set 8-5/8" surface at 1589' w/540 sx Posmix, 2% gen & 150 sx common 2% gel
 DRY & ABANDONED

ELECTRIC LOG TOPS:		ELEVATION:	3392' D. F.
Krider	2193' (/1202)		3384' Gr.
Winfield	2202' (/1193)		3395' K. B.
Council Grove	2537' (/ 858)		
Elmont	3180' (/ 215)		
Topeka	3332' (/ 63)		
Heebner	3608' (- 213)		
Toronto	3636' (- 241)		
Lansing	3678' (-283)		
Marmaton	4270' (- 875)		
Cherokee	4424' (-1029)		
Morrow	4942' (-1547)		
Chester	5330' (-1935)		
St. Gen	5360' (-1965)		
St. Louis	5424' (-2029)		

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 4 1961
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the DICKEY #1, C SW, Sec.15-30S-41W, Stanton County, Kansas, as reflected by the files of Wardco Drilling Company, Inc.

Emil E. Bowers
 Emil E. Bowers

Subscribed and sworn to before me,
 a Notary Public, in and for Sedgwick
 County, Kansas, this 3rd day of May, 1961.

Leah Faye Hefke
 Leah Faye Hefke, Notary Public,

My commission expires June 16, 1963.