


STATE OF KANSAS
CONSERVATION COMMISSION

Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Mc Pherson County. Sec. 12 Twp. 19 Rge. 2 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE SE SE
Lease Owner Alfred Koehn
Lease Name Koehn Well No. I
Office Address Galva, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed Sept 1962
Application for plugging approved Sept 1962
Plugging commenced October 16 1962
Plugging completed October 18 1962
Reason for abandonment of well or producing formation Too much water.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2,992' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
						2,632'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with rock. Rock from 2,992' to 2957'. ~~Mudded hole to~~ Dumped 5 sx of cement. Mudded hole to 160'. Made 10' of rock bridge. Dumped 2 Yrds. of Ready-Mix Cement, filling to the bottom of the cellar.

10-26-62

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address P.O. Box 983 Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 Kings Drive, Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25 th day of October, 1962

My commission expires January 5, 1966
Judy Lamb Notary Public.



N
W E L L R E C O R D

LEASE: Koehn

WELL NO. 1

LOCATION: NE/4 SE/4 SE/4
Sec. 12-19S-2W
McPherson County, Kansas

COMMENCED: 9/27/61

COMPLETED: 10/3/61

OPERATOR: Alfred Koehn
Galva, Kansas

CONTRACTOR: Melland Drilling Company, Inc.
1111 North Main Street
Hutchinson, Kansas

CASING RECORD: 8-5/8" OD casing set at 151' and cemented with 110 sacks.
5-1/2" OD casing set at 2969' and cemented with 50 sacks.

<u>FORMATION</u>	<u>LOG</u>
Surface soil	10
Sand	50
Clay & shale	151
Shale & clay	390
Lime & shale	460
Lime	915
Lime & shale	1205
Shale & shells	1550
Lime & shale	2125
Shale	2280
Lime & shale	2780
Shale & lime	2946
Mississippi Lime	2980
ROTARY TOTAL DEPTH	2980'

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1962

CONSERVATION DIVISION
Wichita, Kansas