

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-113-20,155-00.00

LEASE NAME Nelson

WELL NUMBER 8

990 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 3 TWP. 19 RGE. 2 XXX
(E) or (W)

COUNTY McPherson

Date Well Completed 12/7/71

Plugging Commenced 3/1/91

Plugging Completed 3/5/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hess Oil Company

ADDRESS P. O. Box 1009, McPherson, KS 67460

PHONE# (316) 241-4640 OPERATORS LICENSE NO. 5663

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/1/91 (date)

by Ralph Tittle (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? yes

Producing Formation Mississippi Depth to Top 2927' Bottom T.D. 2962'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

| Formation | Content | From | To | Size | Put in | Pulled out |
|---------------------------|---------|--------------|-----------|---------------|--------------|--------------|
| <u>Surface Production</u> | | <u>150'</u> | <u>0'</u> | <u>8-5/8"</u> | <u>150'</u> | <u>None</u> |
| | | <u>2953'</u> | <u>0'</u> | <u>5-1/2"</u> | <u>2953'</u> | <u>1200'</u> |
| | | | | | | |
| | | | | | | |
| | | | | | | |

MAR 20 1991

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Hole full of mud and junk at 2870'. Sanded to 2860' and ran in 5 sacks cement. Pulled 1200' of 5-1/2" casing out. Built bridge at 260' and filled to surface with 5 yards cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hess Oil Company License No. 5663

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hess Oil Company

STATE OF KANSAS COUNTY OF MCPHERSON, ss.

Dick Hess

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Dick Hess


(Address) same

SUBSCRIBED AND SWORN TO before me this 18th day of March, 19 91

Bryan K Hess
Notary Public

My Commission Expires: _____





Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

October 28, 1971

COMPANY: GEORGE R. HESS
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: NELSON #8
 LOCATION: NW SE SW, Sec. 3-195-2W
 McPherson County, Kansas
 COMMENCED: Oct. 18, 1971
 COMPLETED: Oct. 23, 1971
 ELEVATION:

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1961

McPherson, Kansas

| | | | |
|------|----|------|--------------|
| 0 | to | 35 | Clay |
| 35 | to | 75 | Sand |
| 75 | to | 150 | Shale |
| 150 | to | 525 | Shale & Lime |
| 525 | to | 800 | Lime & Shale |
| 800 | to | 985 | Lime |
| 985 | to | 1405 | Shale & Lime |
| 1405 | to | 1670 | Lime & Shale |
| 1670 | to | 2005 | Lime |
| 2005 | to | 2275 | Lime & Shale |
| 2275 | to | 2334 | Kansas City |
| 2334 | to | 2430 | Shale & Lime |
| 2430 | to | 2690 | Lime |
| 2690 | to | 2927 | Lime & Shale |
| 2927 | to | 2962 | Mississippi |
| | | 2962 | T. D. |

Cut 12 1/4 in. hole to 150 ft. and run 151 ft. of 3 5/8 in. surface pipe, cemented with 100 sacks of cement at 150 ft., plug down at 11:00 A. M., Oct. 18, 1971. Run 7 7/8 in. hole to 2962 ft. Run 2979 ft. of 5 1/2 in. and cemented with 35 sacks of cement, 9 ft. off bottom at 2853 ft., Plug down at 5:45 P. M., October 23, 1971.

TOPS: KANSAS CITY - 2334' MISSISSIPPI - 2927'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your NELSON #8, located on the NW SE SW, Sec. 3-195-2W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe
 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 26th day of October, 1971.

Johann L. Schmidt
 Johann L. Schmidt - Notary Public

